BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/04/2020-21 Dated: 11-08-2020

APPROVED TENDER SCHEDULE –'B'

Item 8

Name of Work :-Improvements to roads and drains at Attur village and Chithra layout surrounding areas in ward no:03

Sl	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri T S Kothanda Raju (Proprietor R K CONSTRUCTIONS, Proprietor SHREE CHARAN CONSTRUCTIONS)	
				Rate	Rate in Words
1	KSRB 300 : Excavation for road, drains and similar works KSRRB 300-1: Earthwork Excavation by manual means for roads, drains and similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per Specifications.	Cum	1396.32	224.97	Two Hundred TwentyFour Paise NinetySeven Only
2	KSRB M2100-10: Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @ 0.89 cum and fine aggregates @ 0.46 cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centring complete as per	cum	204.90	5665.89	Five Thousand Six Hundred SixtyFive Paise EightyNine Only

Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Yelahanka, Division

	Providing and laying in position plain cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregates @ 0.43 cum machine mixed, well compacted for walls and bottom including centring shuttering cost of material HOM of machinary curing etc., complete execuding cost of steel as per Morth Specification no. 1500, 1700, 2000 including cost of material labour HOM complete as per Specifications.	Cum	395.32	7388.36	Seven Thousand Three Hundred EightyEight Paise ThirtySix Only
4	KSRRB M2300-14: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour HOM of machinery complete as per specifications. Specification NO. MORTH Specification No.1600 & 2200 TMT Bars Fe 500.	Tonne	24.28	77321.89	SeventySeven Thousand Three Hundred TwentyOne Paise EightyNine Only
5	Providing and Fixing RCC pre cast cover Slab 100mm thick for drain made out of CC 1:1.5:3 and jelly 20mm Down size with steel reinforcement including form work, lift charges, curing and concrete finished on both sides etc., Complete As per drawing and direction of Engineer IN charge.	Sqm	1076.40	2442.17	Two Thousand Four Hundred FourtyTwo Paise Seventeen Only
6	Providing and Fixing RCC pre cast covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work, laid and lift charges, curing and concrete finished surfaces on both sides etc., complete. As per Engineer IN charge.	Sqm	43.20	5661.81	Five Thousand Six Hundred SixtyOne Paise EightyOne Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.

Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Yelahanka, Division